

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for restoring Bannur Urubagalkere (Kengattekere Reg. No. 185 Sorab Taluk).

No.	Items of work	Per	Quantity
<i>Bund at R. L. 56'00 Top width 4½'</i>			
1	Jungle clearing and cutting grips, etc., complete	Lumpsum	
2	Earthwork for bund including watering tamping complete	C.yd.	1,559
3	Turning the front and rear slopes of bund	Sqr.	303'06
4	Providing and fixing grade stones on a concrete bed of 1'x1'x1' including figuring and painting, etc., complete.	Each	13
	Do do top width stones		13
	Do do Reg. No. and date stones	No.	1
	Do do B. M. stones	Each	2
<i>Constructing a pipe sluice at C. S. 7 R. L. 47'50.</i>			
1	Cutting open the bund pipe portion only	C.yd.	9
2	Refilling the bund with watering and tamping	"	10
3	Earthwork excavation for foundation	"	6
4	Concrete in surki mortar	C.ft.	148
5	Size stone in surki mortar	"	163
6	Burnt stone slabs 6" thick roughly fixed and dressed	S.ft.	47
7	Cement concrete coping over head walls	C.ft.	6
8	Pointing in surki mortar	Sq.	3'00
9	Cutting orifice holes ventway and sill stones in slabs	Lumpsum	
10	Providing a teakwood plug with iron rod including locking arrangement, etc., complete.	"	
11	C. I. pipe 8" dia. with carting and heating joints, etc., complete.	R.ft.	24
<i>Weir in the left flank length 12 feet R. L. 52'00.</i>			
1	Earthwork excavation foundation	C.yd.	21
2	Concrete in surki mortar	C.ft.	101
3	Size stone in surki mortar	"	128
4	Pointing in surki mortar	Sq.	3'00
5	Cement concrete coping and plastered over	C.ft.	19
6	Rough stone work	C.yd.	21

R. H. STEELE,
Executive Engineer.

OFFICE OF THE EXECUTIVE ENGINEER, DAM CONSTRUCTION
AND NO. I CANAL DIVISION, KRASHNARAJASAGARA.

Notice dated 30th June 1930.

The public are hereby informed that the undermentioned unserviceable articles will be sold by auction at the P. W. Store yard commencing at 10 A.M. on the 27th July 1930 and on the following day if necessary.

The highest bidder will be the purchaser. But if proper bids are not forthcoming, the article will not be knocked down. The purchase value of the article should be paid immediately after the sale is effected and the articles removed. Otherwise, the articles sold, will be at the risk of the purchaser.